

Attn. Stuart Smith Eddie Stobart Culina House Stretton Green Distribution Park Langford Way, Appleton Warrington WA4 4TQ

31.01.2022

Dear Mr Stuart Smith,

Ref MF22-1573V2

Thank you for your time in discussing with us your requirement for a safe work area for wet paint spraying and equipment for fitting out your unit to make 6 separate spraying bays

<u>SPECIFICATION</u> Spray Booth Type:	6 x MASTERFLO Dry filter spray booth	
Dimensions:	Extraction Unit: Width: 4080mm Height: 2825mm Depth: 1040mm	
Plenum Body Panels:	1.2mm Galvanised sheet metal of modular design. Turret Punched Pre-Folded and ready for easy bolt–together assembly. Booths to be mounted externally with upturned panels so that water doesn't sit on	
	plenum. Wall sealed with external cloaking set.	
Exhaust Fan:	1 x 4Kw 3 phase Belt Drivel Axial Fan with extraction rate of 16.5m3/s. Spark proof fan and motor. Complete with Fan controller. Exhaust air provided gives 0.7m/sec air flow through the booth face as per HSG140. Speed control invertors to be able to control extraction rate. 16.67Amps Per Fan.	
Lighting:	As each bay will be classified as a spray booth, any lighting or sockets will need to be ATEX approved. The sockets could be placed on isolator switches so that when the booth is in use it cuts the power to the sockets. Not included in price.	
Exhaust Filter:	Filtration is by way of 3 x standard corrugated cardboard dry filter media at 900mm high mounted in the exhaust chamber.	
Exhaust Ducting:	800mm Ducting to exhaust vertically upwards towards atmosphere, terminated with Flap cowl and ducting supported by vertical support and guy rope system.	
Inlet Air/Filters:	Industrial Filtered Louver system either side of the Roller Shutter doors to bring in clean make up air into the spray booth. These are bespoke made so that the correct amount of make air can be brought into the booth to avoid turbulent air and provide a suitable spraying environment. Internal close off door to allow for filter change- By Client.	

Unova Limited, Unit 4 Transcentral, Bennet Road, Reading, RG2 0QX Tel: 01753 584 500 / Fax: 01753 584 501 Email: sales@unovaproducts.com Reg No: 10406638 VAT: 257103522



Fire Exits: Each bay will require minimum 2 fire exits/personnel doors. One by the roller shutter doors at the front and another in the rear wall. Extraction plenum can be placed further to one side to allow for door. Not included in price.

General Specifications:

MaintenanceAll booth systems are supplied with a documented Maintenance
Program. Failure to comply with this may cause warranties to become
null and void.

- **Warranties:** All Equipment included in our proposal will be replaced / repaired for a period of twelve (12) month from practical completion, due to faulty materials, poor workmanship, or inadequate design. Manufacture standards apply to purchased items such as motors, burners, electrical components etc.
- Inclusions:Supply, Deliver & Install 1 x Masterflo Dry Filter Spray Booth System
as specified above. All equipment included in this proposal is subject
to our Standard Terms and conditions of Sale and shall remain the
property of Masterflo Ltd until such time as payment is received in
full.
- Exclusions: All electrical supply/connections and the hire of any access equipment required by installers. Concrete pad for the extraction plenums to be mounted on, and must be above the level of the internal floor level so that water cannot run in once the wall has been cut.

Unova Limited, Unit 4 Transcentral, Bennet Road, Reading, RG2 0QX Tel: 01753 584 500 / Fax: 01753 584 501 Email: sales@unovaproducts.com Reg No: 10406638 VAT: 257103522



MASTERFLO QUOTATION

MASTERFLO MFDF4 6 X Dry Filter Spray Booths (external)	<mark>£47,095.00</mark> *
6 x Fan Speed Control Invertors (4.kw Eac	h) £5,006.40
6 x Iwata Air Fed Mask Kits	£1,554.00
6 x ANI 3 Stage Regulators	£2,058.00
3-year Maintenance package	£348.60 Per Year*

*£3395 + VAT deduction in previous cost

Total = £56,759.20

*Excludes parts

Price Excludes VAT

PAYMENT TERMS:50% Deposit on order30% Prior dispatch20% On Installation

LEAD TIME: 6 - 8 weeks depending on workload at time of order.

All detail and pricing is valid for thirty days from the above date.

To Order – Complete below and Fax to 01753 584501 Or Email <u>sales@masterflo-uk.com</u>

Signed.....

Print.....

Date.....

Kind Regards

Richard Hearn UK Sales Director

Unova Limited, Unit 4 Transcentral, Bennet Road, Reading, RG2 0QX Tel: 01753 584 500 / Fax: 01753 584 501 Email: sales@unovaproducts.com Reg No: 10406638 VAT: 257103522